

BILL OF QUANTITIES

**PROPOSED SEVEN NUMBER CLASSROOMS
ADMINISTRATION BLOCK AT ESSUNZA
PRIMARY SCHOOL**



BILL

Jan-23

COUNTY WORKS OFFICER (MUPW)
VIHIGA DISTRICT
P. O. Box 1460 - 50300 MARAGOLI
Sign: *[Signature]*

[Signature]
DIGITAL CONSTRUCTION
AGENCY LTD.
P.O. Box 110, EMURAYA


| ITEM | DESCRIPTION | QTY | UNIT | RATE | AMOUNT |
|------------------------|--------------------------------------|-----|------|------|--------|
| A | TRANSPORT | | | | |
| B | STORAGE OF MATERIALS | | | | |
| C | MATERIAL TESTING | | | | |
| D | GOVERNMENT ACTS REGARDING WORKPEOPLE | | | | |
| E | INSURANCE | | | | |
| F | OFFICE OF THE PM & CLERK | | | | |
| G | WATER & ELECTRICITY | | | | |
| H | SANITATION | | | | |
| J | PROTECTION OF THE WORKS | | | | |
| K | WORK TO BE DELIVERED UP CLEAN | | | | |
| L | HOARDING | | | | |
| M | GOVERNMENT APPROVALS | | | | |
| TOTAL TO FINAL SUMMARY | | | | | |

| ITEM | DESCRIPTION | UNIT | QTY | RATE | AMOUNT |
|---|--|------|-----|------|---------|
| BILL NO. 1 | | | | | |
| ELEMENT NO. 1: SUBSTRUCTURE (ALL PROVISIONAL) | | | | | |
| EXCAVATION WORKS | | | | | |
| Site preparation | | | | | |
| A | Clear site of works of grass, shrubs, bush and trees, grub up roots, fill with selected soil and burn debris | SM | 680 | 50 | 34 000 |
| B | Excavate to remove top vegetable soil 150mm deep and deposit on the site as described. | SM | 680 | 50 | 34 000 |
| C | Excavate trenches for strip footing not exceeding 1.5m deep commencing at reduced level | CM | 145 | 171 | 24 795 |
| D | Excavate column pits n.e 1.5m deep commencing surface reduced level. | CM | 148 | 171 | 25 308 |
| Disposal | | | | | |
| E | Load and cart away surplus excavated materials from site. | CM | 100 | 520 | 52 000 |
| F | Return, fill and ram selected excavated material around foundation in layers of 150 mm thick maximum. | CM | 193 | 77 | 14 861 |
| Filling | | | | | |
| H | Approved hardcore filling, well watered, rolled and compacted in layers not exceeding 300mm thick | SM | 480 | 87 | 41 760 |
| | 50mm Thick marram blinding to hardcore surfaces. | SM | 480 | 82 | 39 360 |
| Anti-termite treatment | | | | | |
| <i>Apply "Bayer premise 200 sc" or equal and approved insecticide with a ten year guarantee as described.</i> | | | | | |
| K | To surfaces of blinded hardcore. | SM | 480 | 150 | 72 000 |
| Damp proof membrane | | | | | |
| L | Polythene, 1000 gauge; 300 mm laps; no allowance made for laps. | SM | 480 | 85 | 40 800 |
| WATER DISPOSAL | | | | | |
| M | Allow for keeping foundations free from water, mud, fallen materials by pumping, bailing or other approved means, etc. | ITEM | | | 25 000 |
| Planking and strutting | | | | | |
| N | Allow for planking and strutting. | ITEM | | | 25 000 |
| Total Carried Forward | | | | | 42 8884 |

COUNTY WORKS OFFICER (M.O.W.)
 VIHIGA DISTRICT
 P. O. Box 1460 - 50300 MARAGOLI

Sign: *[Signature]*



| ITEM | DESCRIPTION | UNIT | QTY | RATE | AMOUNT |
|------|---|------|-------|-------|---------|
| | Total Brought Forward | | | | 428884 |
| | INSITU REINFORCED CONCRETE | | | | |
| | <u>50mm Thick mass concrete 1:4:8 class 15/20 in:</u> | | | | |
| A | Ditto ; columns bases | SM | 180 | 400 | 72000 |
| | <u>Class 20 Vibrated Reinforced concrete as described in:-</u> | | | | |
| C | Column bases & columns | CM | 35 | 12359 | 432565 |
| D | 150mm Thick surface slab. | SM | 480 | 1859 | 892320 |
| | REINFORCEMENTS | | | | |
| | <u>High yield square twisted rod reinforcement to BS 4461 in structural concrete work including cutting bending hoisting, fixing, tying wire and spacing blocks to:</u> | | | | |
| | 10mm | KG | 1,100 | 120 | 132000 |
| E | 16mm diameter | KG | 1,320 | 120 | 158400 |
| F | Ditto 8mm | KG | 210 | 120 | 25200 |
| G | ditto 12mm | KG | 1,120 | 120 | 134400 |
| | <u>Fabric; BS 4483 Reference A142; mesh 200 x 200 mm weight 2.2 kg per sm (300 mm laps); including bends , tying wire and distance blocks.</u> | | | | |
| F | In concrete surface slab. | SM | 480 | 358 | 171840 |
| | Sawn timber formwork as described | | | | |
| G | To edges of surface slab 75 - 150mm high. | LM | 125 | 58 | 7250 |
| H | Sides of column bases | SM | 230 | 385 | 88550 |
| | Walling | | | | |
| | <u>Load bearing natural stone walling, jointed in cement and sand (1:3) mortar with and including No.20 gauge hoop iron ties 450mm long x 25mm wide bent and tacked into formwork with one end cast into concrete and straightened after removal of formwork and built into mortar joint of walling</u> | | | | |
| M | 200mm Thick walling: | SM | 300 | 1200 | 360000 |
| | PLINTH FINISHES | | | | |
| | <u>Waterproof render in:-</u> | | | | |
| N | 15 mm Thick wood float finished to plinths. | SM | 60 | 225 | 13500 |
| | Paint & Decorations | | | | |
| P | Prepare surfaces and apply three coats bituminous paint to rendered surfaces (m/s). | SM | 60 | 225 | 13500 |
| | Carried Forward to Summary of Bill No.02 | | | | |
| | Bill No. 01 Ground Floor Element No.01 Substructures. | | | | 2930409 |



| ITEM | DESCRIPTION | UNIT | QTY | RATE | AMOUNT |
|--|--|------|-------|------|---------|
| ELEMENT NO. 2: CONCRETE FRAME/ WALLING | | | | | |
| WALLING | | | | | |
| External Walls | | | | | |
| | Chisel dressed natural stone walling jointed in cement/sand mortar mix 1:3 including 25 x 4mm thick hoop iron at every alternate courses | | | | |
| A | 200 mm Thick external walls | SM | 320 | 1100 | 352,000 |
| INTERNAL WALLS | | | | | |
| | Machine cut stone walling jointed in cement/sand mortar mix 1:3 including 25 x 4mm thick hoop iron at every alternate courses | | | | |
| B | 150mm Thick walls | SM | 200 | 950 | 190,000 |
| Horizontal damp proof course: one layer of 3- ply bituminous felt or other equal and approved (measured nett - allow for laps) | | | | | |
| | 200mm wide levelled and bedded in cement and sand (1:3) mortar under walls | | | | |
| C | | LM | 180 | 100 | 18,000 |
| In situ concrete class 25/20, vibrated and reinforced as described, in:- | | | | | |
| D | Columns | CM | 20 | 9524 | 190880 |
| E | Beams | CM | 55 | 9544 | 524920 |
| F | Stairs AND ramp | CM | 22 | 9544 | 209968 |
| G | 150mm thick Suspended slab | SM | 400 | 1432 | 572800 |
| REINFORCEMENTS | | | | | |
| High yield square twisted rod reinforcement to BS 4461 in structural concrete work including cutting bending, hoisting, fixing, tying wire and spacing blocks to: | | | | | |
| J | 10mm diameter | KG | 3,800 | 120 | 456000 |
| K | Ditto 16mm diameter | KGS | 3,650 | 120 | 438000 |
| L | Ditto 12mm | KGS | 720 | 120 | 86400 |
| M | Ditto 8mm | KGS | 2,100 | 120 | 252,000 |
| Sawn formwork: to | | | | | |
| N | Vertical Sides of Columns | SM | 200 | 385 | 77000 |
| O | Soffits and sides of beams | SM | 870 | 385 | 334950 |
| C | Formwork to the soffits of the suspended slab. | SM | 396 | 385 | 152460 |
| Total Carried Forward | | | | | |

COUNTY WORKS OFFICER (MOPW)
 VIHIGA DISTRICT
 P. O. Box 1460 - 50200 MARAGOLI
 Sign: *[Signature]*


[Signature]
GILGAL CONSTRUCTION
AGENCY LTD.
 P.O. Box 110, EMUHAYA

| ITEM | DESCRIPTION | UNIT | QTY | RATE | AMOUNT |
|---|---|------|-----|------|---------|
| ELEMENT NO 4-ROOFING | | | | | |
| A | 28 gauge Prepainted G.C.I sheets nailed | SM | 560 | 650 | 364000 |
| B | 28 gauge ridge cap | LM | 110 | 575 | 62150 |
| <u>The following in swan calcured cypress</u> | | | | | |
| C | 150 x 50 mm rafters | LM | 550 | 300 | 165000 |
| D | 150 x 50 mm Tie Beam | LM | 420 | 300 | 126000 |
| E | 100 x 50 mm struts / ties | LM | 400 | 200 | 80000 |
| F | 100 x 50 mm Kingpost | LM | 200 | 200 | 40000 |
| G | 150 x 50 mm wallplate | LM | 150 | 300 | 45000 |
| H | 75 x 50 mm purlins | LM | 500 | 145 | 72500 |
| J | 225 x 25 mm fascia board | LM | 122 | 200 | 24400 |
| K | Prepare and apply two under coats and one finishing coat of exterior quality super gloss oil paint to wood surfaces 200-300mm girth | LM | 122 | 50 | 6100 |
| <u>RAIN WATER DISPOSAL</u> | | | | | |
| L | 140mm Diameter half round plastic gutter | LM | 120 | 260 | 31200 |
| M | 75mm plastic downpipe | LM | 50 | 170 | 8500 |
| N | Extra over down pipe for swan neck | NO | 12 | 170 | 2040 |
| O | Extra over down pipe for shoe | NO | 12 | 170 | 2040 |
| TOTAL FOR ROOFING CARRIED TO SUMMARY | | | | | 1028930 |

COUNTY WORKS OFFICER (MOPW)
 VIHIGA DISTRICT
 P. O. Box 1460 - 50009 MARAGOLI
 Sign: *[Signature]*




| ITEM | DESCRIPTION | UNIT | QTY | RATE | AMOUNT |
|---|--|------|-----|------|--------|
| ELEMENT NO. 4: WINDOWS. | | | | | |
| <i>Supply, assemble and fix primed purpose made heavy duty mild steel window comprising standard steel window frame built in wall, 25 x 25 mm Z section frame welded to standard frame in small panes complete with and including permanent ventilators comprising T-bars, gauze and metal hood, coupling mullions: oiling and adjusting on completion and fixing of ironmongery such as hinges, locking devices such as windows fasteners, stays locks, bolts etc; all to Architect's approval and in accordance with drawings</i> | | | | | |
| A | Window size 1500 x 1500mm high overall | NO | 40 | 8000 | 320000 |
| B | Window size 600 x 600mm high overall | NO | | | |
| C | Window size 1000 x 900mm high overall (W01) | NO | - | | |
| D | Window size 2350 x 700mm high overall (W01) | NO | - | | |
| E | Window size 2950 x 700mm high overall (W01) | NO | | | |
| Glazing | | | | | |
| <i>6mm Thick Clear glass and glazing fixed with and including putty to steel windows (m.s)</i> | | | | | |
| F | Panes 0.1 - 0.5 square metres | SM | 120 | 1210 | 145200 |
| PAINTING AND DECORATING | | | | | |
| <i>Apply one coat and two finishing coats of gloss oil paint as "Crown Paints" or other approved to metal work in:</i> | | | | | |
| G | General surfaces of windows both sides. | SM | 120 | 200 | 24000 |
| Curtain Rods | | | | | |
| J | 25mm Diameter approved wrought iron front and rear rod curtain rail cut to lengths complete with fixings, runners and end stops and screwed or plugged to wall in accordance with the manufacturer's specifications. | LM | 110 | 2500 | 275000 |
| Carried Forward to Summary of Bill No.02 | | | | | |
| Bill No. 01 Ground Floor Element No.03 Windows | | | | | 764200 |




| ITEM | DESCRIPTION | UNIT | QTY | RATE | AMOUNT |
|------|---|------|-----|-------|--------|
| | ELEMENT NO. 5: DOORS Note: All doors to architect's approval and drawing details | | | | |
| | STEEL DOORS <i>Supply, assemble and fix primed purpose French steel doors comprising heavy duty mild steel frame built into wall, oiling and adjusting on completion and fixing of ironmongery such as hinges, locking devices etc; all to Architect's approval and in accordance with drawings</i> | | | | |
| A | Door overall size 1200 x 2400mm high. | NO | 8 | 20000 | 160000 |
| B | Door overall size 900 x 2400mm high. | NO | | | |
| | TIMBER DOORS Door frames <i>Supply, assemble and fix the following purpose mild steel door frame and including one coat of approved red oxide primer by the manufacturer before delivery on site building and bedding frames in concrete columns. The door frames shall conform in every respect with drawings bracketed after item descriptions all to the approval of the Architect.</i> | | | | |
| C | 100x50mm door frame including architrave and quadrant | LM | 300 | 850 | 225000 |
| | Flush doors <i>45 mm Thick semi solid flush door faced both sides with high interior quality plywood with 50 x 12 mm thick hard wood lipping all round.</i> | | | | |
| D | Door overall size 900 x 2400 mm high. | NO | 8 | 3000 | 24000 |
| E | Door overall size 800 x 2100mm high | No. | | | |
| | Paint & Decorations <i>Apply one coat and two finishing coats of polyurethane clear varnish as to wood work in:</i> | | | | |
| F | General surfaces. | SM | 300 | 200 | 6000 |
| | <i>Apply one coat and two finishing coats of gloss oil paint as "Crown Paints" or other approved to metal work in:</i> | | | | |
| G | Framing, generally | LM | 300 | 200 | 60000 |
| H | General surfaces of doors both sides. | SM | 150 | 2000 | 30000 |
| | IRON MONGERY <i>Supply and fix the following UNION ironmongery or other equal and approved ironmongery complete with all matching screws and keys (Reference to this particular catalogue is given as a guide to type and quality only and equal and approved alternatives may be used)</i> | | | | |
| J | 100mm brass butt hinges | Prs | 8 | 310 | 2480 |
| K | Two lever mortice lock with pair of lever handles | No | 8 | 2150 | 17200 |
| L | Ditto but steel locks | No. | | | |
| M | Rubber Door Stop | No | 8 | 160 | 1280 |
| | Carried Forward to Summary of Bill No.02 | | | | |
| | Bill No. 01 Ground Floor Element No. 5 Doors | | | | 609960 |

COUNTY WORKS OFFICER (MOPW)
VIHIGA DISTRICT
P. O. Box 1460 - 50200 MARAGOLI
Sign: *[Signature]*



| ITEM | DESCRIPTION | UNIT | QTY | RATE | AMOUNT |
|---|---|------|-----|-------|--------|
| ELEMENT NO. 5: DOORS | | | | | |
| Note: All doors to architect's approval and drawing details | | | | | |
| STEEL DOORS | | | | | |
| <i>Supply, assemble and fix primed purpose French steel doors comprising heavy duty mild steel frame built into wall, oiling and adjusting on completion and fixing of ironmongery such as hinges, locking devices etc; all to Architect's approval and in accordance with drawings.</i> | | | | | |
| A | Door overall size 1200 x 2400mm high. | NO | 8 | 20000 | 160000 |
| B | Door overall size 900 x 2400mm high. | NO | | | |
| TIMBER DOORS | | | | | |
| Door frames | | | | | |
| <i>Supply, assemble and fix the following purpose mild steel door frame and including one coat of approved red oxide primer by the manufacturer before delivery on site building and bedding frames in concrete columns. The door frames shall conform in every respect with drawings bracketed after item descriptions all to the approval of the Architect.</i> | | | | | |
| C | 100x50mm door frame including architrave and quadrant | LM | 300 | 850 | 225000 |
| Flush doors | | | | | |
| <i>45 mm Thick semi solid flush door faced both sides with high interior quality plywood with 50 x 12 mm thick hard wood lipping all round.</i> | | | | | |
| D | Door overall size 900 x 2400 mm high. | NO | 8 | 3000 | 24000 |
| E | Door overall size 800 x 2100mm high | No. | | | |
| Paint & Decorations | | | | | |
| <i>Apply one coat and two finishing coats of polyurethane clear varnish as to wood work in:</i> | | | | | |
| F | General surfaces. | SM | 300 | 200 | 6000 |
| <i>Apply one coat and two finishing coats of gloss oil paint as "Crown Paints" or other approved to metal work in:</i> | | | | | |
| G | Framing; generally | LM | 300 | 200 | 60000 |
| H | General surfaces of doors both sides. | SM | 150 | 2000 | 30000 |
| IRON MONGERY | | | | | |
| <i>Supply and fix the following UNION ironmongery or other equal and approved ironmongery complete with all matching screws and keys (Reference to this particular catalogue is given as a guide to type and quality only and equal and approved alternatives may be used)</i> | | | | | |
| J | 100mm brass butt hinges | Prs | 8 | 310 | 2480 |
| K | Two lever mortice lock with pair of lever handles | No | 8 | 2150 | 17200 |
| L | Ditto but steel locks | No. | | | |
| M | Rubber Door Stop | No | 8 | 160 | 1280 |
| Carried Forward to Summary of Bill No.02 | | | | | |
| Bill No. 01 Ground Floor Element No. 5 Doors | | | | | 609960 |

COUNTY WORKS OFFICER (MOPW)
VIHIGA DISTRICT
P. O. Box 1469 - 53339 MARAGOLI
Sign: *[Signature]*



| ITEM | DESCRIPTION | UNIT | QTY | RATE | AMOUNT |
|---|---|------|-----|------|--------|
| ELEMENT NO. 6: WALL FINISHES | | | | | |
| EXTERNAL FINISHES | | | | | |
| A | External horizontal and vertical keying | SM | 350 | 250 | 87500 |
| Internal finishes | | | | | |
| Wall Finishes | | | | | |
| <i>Prepare and apply two coats of joint paste plaster to wall surfaces to Architect's Approval as described in:-</i> | | | | | |
| E | General wall surfaces. | SM | 530 | 250 | 132500 |
| Painting and Decoration | | | | | |
| <i>Apply one coat and two finishing coats of silk vinyl/emulsion paint as "Crown Paints" or other equal and approved to:-</i> | | | | | |
| F | Plastered wall surfaces. | SM | 530 | 200 | 106000 |
| <i>15mm thick cement and sand (1:4) backing as described to:-</i> | | | | | |
| G | Sides of walls to receive mazeras wall finish (m.s) | SM | | | |
| <i>Supply & fix approved ceramic wall tiles fixed on backing (measured separately) with an approved adhesive jointed and flush pointed with grouting to match tile all to Architect's approval.</i> | | | | | |
| H | General wall surfaces in wet areas | SM | 30 | 800 | 24000 |
| Carried Forward to Summary of Bill No.02 | | | | | |
| Bill No. 01 Ground Floor Element No. 06 Wall Finishes | | | | | 350000 |




| ITEM | DESCRIPTION | UNIT | QTY | RATE | AMOUNT |
|---|--|------|-----|------|---------|
| ELEMENT NO 7: FLOOR FINISHES. | | | | | |
| <u>Floor Finishes</u> | | | | | |
| <u>Screed, Backing & Skirting.</u> | | | | | |
| <u>In situ cement sand (1:3) screeded beds with wood floated finish, on concrete to:-</u> | | | | | |
| A | 25mm Thick floor backing | SM | 960 | 400 | 384000 |
| B | Ditto to 100mm high skirting | LM | 200 | 35 | 7000 |
| <u>Terrazo</u> | | | | | |
| C | 20mm thick polished terrazo finish with dividing strip moulded in cement and sand mortar (1:3) Including plastic | SM | 960 | 850 | 816000 |
| D | 100mm high skirting | LM | 200 | 85 | 17000 |
| Carried Forward to Summary of Bill No.02 | | | | | |
| Bill No. 01 Ground Floor Element No. 07 Floor Finishes | | | | | 1224000 |

COUNTY WORKS OFFICER (MOPWA)
VIHIGA DISTRICT
P. O. Box 1460 - 53300 MARAGOLI
Sign: *[Signature]*



| ITEM | DESCRIPTION | UNIT | QTY | RATE | AMOUNT |
|---|---|------|-------|------|---------|
| ELEMENT NO.8 : CEILING FINISHES. | | | | | |
| <u>Ceiling Finishes</u> | | | | | |
| <u>Prepare and apply two coats of joint paste plaster to Architect's Approval as described in:-</u> | | | | | |
| A | Soffits of the suspended slab. | SM | 480 | 250 | 120 000 |
| <u>PAINING AND DECORATING</u> | | | | | |
| <u>Prepare and apply two coats of premium quality emulsion paint to:-</u> | | | | | |
| B | Plastered concrete soffits | SM | 480 | 200 | 96 000 |
| C | 13mm thick chip board ceiling laid on 50x50mm timber brandering | SM | 480 | 530 | 264 000 |
| D | Wrot cypress 50x50mm timber brandering at 600 centres | LM | 1,500 | 100 | 150 000 |
| Carried Forward to Summary of Bill No.02 | | | | | |
| Bill No. 01 Ground Floor Element No.8 Ceiling Finishes. | | | | | 630,000 |



| ITEM | DESCRIPTION | UNIT | QTY | RATE | AMOUNT |
|------|---|------|-----|------|------------|
| | <u>SUMMARY</u> | | | | |
| | Sub structures: Total Brought Forward | | | | 2,930,409 |
| | Concrete Frame & Walling: Total Brought Forward | | | | 3,855,378 |
| | Roofing: Total Brought Forward | | | | 1,028,930 |
| | Windows: Total Brought Forward | | | | 764,200 |
| | Doors : Total brought forward | | | | 609,960 |
| | Wall Finishes: Total brought forward | | | | 350,000 |
| | Floor Finishes: Total brought forward | | | | 1,224,000 |
| | Ceiling Finishes: Total brought forward | | | | 630,000 |
| | Carried Forward to Final Summary | | | | 11,392,877 |
| | Bill No. 1 | | | | |
| | Ground Floor. | | | | |


WORKS OFFICER (MOPW)
 VINDIGA DISTRICT
 P. BOX 1460 - 50200 MARAGOLI
 SIGN: *[Signature]*

[Signature]

**SILGAL CONSTRUCTION
 AGENCY LTD.
 P.O. BOX 110, EMUHAYA**

| ITEM | DESCRIPTION | UNIT | QTY | RATE | AMOUNT |
|--|--|------|-----|------|---------------------|
| BILL NO. 01 | | | | | |
| PROVISIONAL & PRIME COST SUMS | | | | | |
| ELECTRICAL WORKS | | | | | |
| A | Allow a provisional sum of KSH Three Hundred thousand only (Kshs.300,000) for Electrical Installations | Sum | | | 300,000.00 |
| MECHANICAL WORKS | | | | | |
| B | Allow a provisional sum of Kenya shillings Three Hundred Thousand Only (Kshs. 300,000) Only for Mechanical Installations | Sum | | | 300,000.00 |
| PROJECT MANAGEMENT | | | | | |
| D | Allow a Provisional sum of Kenya Shillings Two Hundred Thousand (300,000) Only for Engineers Misceleneous. | Sum | | | 300,000.00 |
| CONTINGENCY | | | | | |
| E | Allow a Provisional sum of Kenya Shillings Five Hundred Thousand (300,000) Only for Contingency. | Sum | | | 300,000.00 |
| PLUMBING WORKS AND DRAINAGE WORKS | | | | | |
| G | Allow a provisional sum of Ksh. Two Hundred thousand 200,000.00for plumbing and drainage works | | | | 200,000.00 |
| WATER TANKS | | | | | |
| J | Allow a provisional sum of Ksh. One Hundred and Fifty thousand (150,000) for water tank | | | | 150,000.00 |
| K | <u>General Contract office and administrative cost</u> | | | | 1,000,000.00 |
| Carried Forward to Final Summary | | | | | 2,550,000.00 |
| Bill No.1 | | | | | |
| P.C & PROVISIONAL SUM | | | | | |

[Handwritten Signature]



 GLOBAL CONSTRUCTION
 AGENCY LTD.
 P.O. Box 110, NAIROBI, KENYA

| ITEM | DESCRIPTION | PAGE | AMOUNT (SHS) |
|--|--------------------------|------|----------------------|
| GRAND SUMMARY | | | |
| 1 | PRELIMINARIES | | 250,000 |
| 2 | BUILDERS WORK | | 11,392,877 |
| 3 | P.C AND PROVISIONAL SUMS | | 2,550,000.00 |
| SUB TOTAL | | | 14,192,877 |
| ADD 16% VAT | | | 2,270,861 |
| TOTAL ESTIMATED COST OF THE PROJECT | | | 16,463,738.00 |

TENDERER

Signature 

Name & Title 

Date

Official Stamp

EMPLOYER

Signature 

Name & Title

Date

Official Stamp

COUNTY WORKS OFFICER (MOPW)
 VIHIGA DISTRICT
 P. O. Box 1462 - 53200 MARACOTI
 Sign. 