

REPUBLIC OF KENYA



MINISTRY OF TRANSPORT, INFRASTRUCTURE, PUBLIC WORKS, HOUSING AND URBAN DEVELOPMENT

STATE DEPARTMENT OF PUBLIC WORKS

BILLS OF QUANTITIES

FOR

**PROPOSED CONSTRUCTION OF PROPOSED CONSTRUCTION OF A 6NO, ONE
STOREY BUILDING CLASSROOMS, AN ADMINISTRATION BLOCK AND A 4
DOOR ABLUTION BLOCK AT MUKARARA MIXED SECONDARY SCHOOL IN
DAGORETTI SOUTH CONSTITUENCY.**

TENDER NO.: DS-NGCDF-MMSS-20/21

ISSUED BY:

**REGIONAL WORKS OFFICER
NAIROBI REGION
P.O. BOX 42267
NAIROBI**

PREPARED BY:

**REGION ARCHITECT
NAIROBI REGION
P.O. BOX 42267
NAIROBI**

**REGION QUANTITY SURVEYOR
NAIROBI REGION
P.O. BOX 42267
NAIROBI**

JULY, 2020

ITEM	DESCRIPTION	K.SHS
	PARTICULAR PRELIMINARIES	
A	PRICING ITEMS OF PRELIMINARIES Prices SHALL BE INSERTED against items of "preliminaries" in the tenderer's priced Bills of Quantities. The contractor is advised to read and understand all preliminary items.	
B	DESCRIPTION OF THE WORKS The works to be carried out under this contract involves; CONSTRUCTION OF SIX CLASSROOMS, ABLUTION BLOCK AND ADMINISTRATION BLOCK. The structures are constructed of reinforced concrete framed structure infilled with natural stone walls.	
C	MEASUREMENTS In the event of any discrepancies arising between the Bills of Quantities and the actual works, the site measurements shall generally take precedence. However, such discrepancies between any contract documents shall immediately be referred to the PROJECT	
D	LOCATION OF SITE The site of the proposed works is located in located at in Dagoretti South constituency. The Contractor is advised to visit the site, to familiarize with the nature and position of the site. No claims arising from the Contractor's failure to do so will be entertained.	
E	SIGNING OF THE TENDER DOCUMENTS The bidder shall append his / her signature and / or company 's rubberstamp on each and every page of tender document.	
	<i>Carried to collection</i>	

ITEM	DESCRIPTION	K.SHS
A	<p>DEMOLITIONS AND ALTERATIONS</p> <p>The Contractor is to allow for all temporary protection required during the works including ordinary and special dust screens, hoardings, barriers, warning signs, etc as directed by the Project Manager and</p> <p>as necessary for the adequate propping and protection of existing property, finishes, workmen employed on the site, employer's agents and the public. Any damage or loss incurred due to the insufficiency of such protection must be made good by the Contract</p> <p>The works shall be propped, strutted and supported as necessary before any alteration or demolition work commences. Prices shall include for all cleaning and preparatory work to structure and finishes and for making good to all finishes on completion whet</p> <p>Unless described as set aside for re-use all arising debris and surplus materials shall be carefully removed from building and carted away from site.</p> <p>The Contractor shall be entirely responsible for any breakage or damage which may occur to materials required for re-use during their removal unless it is certified by the Project Manager that such damage or breakage was inevitable as a result of the cond</p>	
B	<p>CLEARING AWAY</p> <p>The Contractor shall remove all temporary works, rubbish, debris and surplus materials from the site as they accumulate and upon completion of the works, remove and clear away all plant, equipment, rubbish, unused materials and stains and leave in a clean</p> <p>The whole of the works shall be delivered up clean, complete and in perfect condition in every respect to the satisfaction of the Project Manager.</p>	50,000.00
C	<p>CLAIMS</p> <p>It shall be a condition of this contract that upon it becoming reasonably apparent to the Contractor that he has incurred losses and / or expenses due to any of the contract conditions, or by any other reason whatsoever, he shall present such a claim or intent to claim notice to the PROJECT MANAGER within the contract period. No claim shall be entertained upon the expiry of the said contract period.</p>	
	<i>Carried to collection</i>	

ITEM	DESCRIPTION	K.SHS
	<u>PARTICULAR PRELIMINARIES</u>	
A	PRICING ITEMS OF PRELIMINARIES Prices <u>SHALL BE INSERTED</u> against items of "preliminaries" in the tenderer's priced Bills of Quantities. The contractor is advised to read and understand all preliminary items.	
B	DESCRIPTION OF THE WORKS The works to be carried out under this contract involves; CONSTRUCTION OF SIX CLASSROOMS, ABLUTION BLOCK AND ADMINISTRATION BLOCK. The structures are constructed of reinforced concrete framed structure infilled with natural stone walls.	
C	MEASUREMENTS In the event of any discrepancies arising between the Bills of Quantities and the actual works, the site measurements shall generally take precedence. However, such discrepancies between any contract documents shall immediately be referred to the PROJECT	
D	LOCATION OF SITE The site of the proposed works is located in located at in Dagoretti South constituency. The Contractor is advised to visit the site, to familiarize with the nature and position of the site. No claims arising from the Contractor's failure to do so will be entertained.	
E	SIGNING OF THE TENDER DOCUMENTS The bidder shall append his / her signature and / or company 's rubberstamp on each and every page of tender document.	
	<i>Carried to collection</i>	

ITEM	DESCRIPTION	K.SHS
A	<p>DEMOLITIONS AND ALTERATIONS</p> <p>The Contractor is to allow for all temporary protection required during the works including ordinary and special dust screens, hoardings, barriers, warning signs, etc as directed by the Project Manager and</p> <p>as necessary for the adequate propping and protection of existing property, finishes, workmen employed on the site, employer's agents and the public. Any damage or loss incurred due to the insufficiency of such protection must be made good by the Contract</p> <p>The works shall be propped, strutted and supported as necessary before any alteration or demolition work commences. Prices shall include for all cleaning and preparatory work to structure and finishes and for making good to all finishes on completion whet</p> <p>Unless described as set aside for re-use all arising debris and surplus materials shall be carefully removed from building and carted away from site.</p> <p>The Contractor shall be entirely responsible for any breakage or damage which may occur to materials required for re-use during their removal unless it is certified by the Project Manager that such damage or breakage was inevitable as a result of the cond</p>	-
B	<p>CLEARING AWAY</p> <p>The Contractor shall remove all temporary works, rubbish, debris and surplus materials from the site as they accumulate and upon completion of the works, remove and clear away all plant, equipment, rubbish, unused materials and stains and leave in a clean</p> <p>The whole of the works shall be delivered up clean, complete and in perfect condition in every respect to the satisfaction of the Project Manager.</p>	50,000.00
C	<p>CLAIMS</p> <p>It shall be a condition of this contract that upon it becoming reasonably apparent to the Contractor that he has incurred losses and / or expenses due to any of the contract conditions, or by any other reason whatsoever, he shall present such a claim or intent to claim notice to the PROJECT MANAGER within the contract period. No claim shall be entertained upon the expiry of the said contract period.</p>	
	<i>Carried to collection</i>	

ITEM	DESCRIPTION	K.SHS
A	PAYMENTS The tenderer's attention is drawn to the fact that the GOVERNMENT DOES NOT MAKE ADVANCE PAYMENTS but pays for work done and materials delivered to sit: all in accordance with Clause 23 of the Conditions of Contract Agreement. In order to facilitate this,	
B	PREVENTION OF ACCIDENT, DAMAGE OR LOSS The Contractor is notified that these works are to be carried out on a restricted site where the client is going on with other normal activities. The Contractor is thus instructed to take reasonable care in the execution of the works as to prevent accident	
C	WORKING CONDITIONS The Contractor shall allow in his rates for any interference that he may encounter in the course of the works for the Client may in some cases ask the Contractor not to proceed with the works until some activities within the site are completed, as the fac	
D	SIGNBOARD Allow for providing, erecting, maintaining throughout the course of the Contract and afterwards clearing away a signboard as designed, specified and approved by the Project Manager.	30,000.00
E	LABOUR CAMPS The Contractor shall not be allowed to house labour on site. Allow for transporting workers to and from the site during the tenure of the contract.	
F	MATERIALS FROM DEMOLITIONS Any materials arising from demolitions and not re-used shall become the property of the Ministry of Public Works. The Contractor shall allow in his rates the cost of transporting the demolished materials to the Provincial Works Office.	
	<i>Carried to collection</i>	30,000.00

ITEM	DESCRIPTION	K.SHS
A	PRICING RATES The tenderer shall include for all costs in executing the whole of the works, including transport, replacing damaged items, fixing, all to comply with the said Conditions of Contract.	
B	SECURITY The Contractor shall allow for providing adequate security for the works and the workers in the course of execution of this contract. No claim will be entertained from the Contractor for not maintaining adequate security for both the works and workers.	50,000.00
C	URGENCY OF THE WORKS The Contractor is notified that these "works are urgent" and should be completed within the period stated in these Particular Preliminaries. The Contractor shall allow in his rates for any costs he/she deems that he/she may incur by having to complete these works within the stipulated contract period.	
D	PAYMENT FOR MATERIALS ON SITE All materials for incorporation in the works must be stored on site before payment is effected, unless specifically exempted by the Project Manager. This is to include materials of the Contractor, nominated sub-Contractors and nominated suppliers.	
E	EXISTING SERVICES Prior to the commencement of any work, the Contractor is to ascertain from the relevant authority the exact position, depth and level of all existing services in the area and he/she shall make whatever provisions may be required by the authorities concern	
F	BID SECURITY The Bidder shall furnish, as part of his bid, a security as specified in the tender advertisement. The bid security shall, at the bidder's option, be in the form of a certified cheque, bank draft, standby letter of credit or guarantee from a reputable bank located in Kenya or foreign bank which has been determined by the bidder to be acceptable to the Guarantees issued as surety for the bid shall be valid for a period of One Hundred and Twenty (120) days from the date of Tender Opening.	
	<i>Carried to collection</i>	50,000.00

ITEM	DESCRIPTION	K.SHS
A	<p>PERFORMANCE BOND</p> <p>A bond of 5% of the contract sum will be required in accordance with clause 6.00 (as amended) on award of contract of the Instructions to Tenderer's. No payment on account for the works executed will be made to the contractor until he has submitted the Performance Bond.</p>	
B	<p>TENDER DOCUMENTS</p> <p>Tender documents are as listed in Clause 2.1 of the Instruction to Tenderer's Page STD/8</p>	
A	<p>DELIVERY OF TENDER</p> <p>Tenders and all documents in connection therewith, as specified above must be delivered in the addressed envelope which should be properly sealed and deposited at the offices as specified in the letter accompanying these documents or as indicated in t</p> <p>Tenders will be opened at the time specified in the letter accompanying these Tender Documents or as indicated in the advertisement. Tenders delivered/received later than the above time will not be opened.</p>	
C	<p>VALUE ADDED TAX</p> <p>The Contractor's attention is drawn to the Legal Notice in the Finance Act part 3 Section 21(b) operative from 1st September, 1993 which requires payment of VAT on all contracts. The Contractor should therefore include allowance in his rates and prices fo</p> <p>The tenderer is advised that in accordance with Government public notice No. 35 & 36 Dated 11th September 2003 operational from 1st October 2003, VAT will be deducted against the contract sum at the prevailing rate by the Employer and remitted directly to</p> <p>NB: VAT SHALL be added at the Grand summary page (GS/1)</p>	
	<i>Carried to collection</i>	

ITEM	DESCRIPTION	K.SHS
A	<p data-bbox="301 62 1050 136">PARTICULARS OF INSERTIONS TO BE MADE IN APPENDIX TO CONTRACT AGREEMENT</p> <p data-bbox="301 136 1118 192">The following are the insertions to be made in the appendix to the Contract Agreement: -</p> <p data-bbox="301 215 975 271">Period of Final Measurement 3 Months From Practical completion</p> <p data-bbox="301 271 975 327">Defects Liability Period 6 Months from Practical completion</p> <p data-bbox="301 327 967 383">Date for Possession To be agreed with the Project Manager</p> <p data-bbox="301 383 948 439">Date for Completion Weeks from date of Possession</p> <p data-bbox="301 439 948 495">Liquidated and Ascertained At the rate of Kshs.. 35,000... per week or part thereof</p> <p data-bbox="301 495 911 528">Prime cost sums for which</p> <p data-bbox="301 528 911 562">The Contractor desires to tender</p> <p data-bbox="301 562 839 618">Period of Interim Certificates Monthly</p> <p data-bbox="301 618 847 674">Period of Honouring Certificates 30 days</p> <p data-bbox="301 674 815 730">Percentage of Certified Value Retained 10%</p> <p data-bbox="301 730 807 786">Limit of Retention Fund 5%</p> <p data-bbox="636 1659 839 1693"><i>Carried to collection</i></p>	

ITEM	DESCRIPTION	K.SHS
	<u>COLLECTION</u>	
	Brought forward from page PP/1	
	Brought forward from page PP/2	
	Brought forward from page PP/3	30,000.00
	Brought forward from page PP/4	50,000.00
	Brought forward from page PP/5	
	Brought forward from page PP/6	600,000.00
	Brought forward from page PP/7	
	TOTAL FOR PARTICULAR PRELIMINARIES CARRIED TO SUMMARY OF PRELIMINARIES	680,000.00

ITEM	DESCRIPTION	AMOUNT
A.	<p>EXCEPTION TO THE STANDARD METHOD OF MEASUREMENT</p> <p><i>Attendance ; Clause B19(a) of the Standard Method of Measurement is deleted and the following clause is substituted:-</i></p> <p>Attendance on nominated Sub-Contractors shall be given as an item in each case shall be deemed to include: allowing use of standing scaffolding, mess rooms, sanitary accommodation and welfare facilities; provision of special scaffolding where necessary; providing space for office accommodation and for storage of plant and materials; providing light and water for their work; clearing away rubbish; unloading checking and hoisting; providing electric power and removing and replacing duct covers, pipe casings and the like necessary for the execution and testing of Sub- Contractors' work and being responsible for the accuracy of the same.</p> <p><i>Fix Only:-</i></p> <p>"Fix Only" shall mean take delivery at nearest railway station (Unless otherwise stated),pay all demurrage charges, load and transport to site where necessary, unload, store,unpack, assemble as necessary, distribute to position, hoist and fix only.</p>	
B.	<p>EMPLOYER</p> <p>The "Employer" is The NATIONAL GOVERNMENT CONSTITUENCY DEVELOPMENT FUND MANAGER-DAGORETTI SOUTH CONSTITUENCY.</p>	
C.	<p>PROJECT MANAGER</p> <p>The term "P.M." wherever used in these Bills of Quantities shall be deemed to imply the Project Manager as defined in Condition 1 of the Conditions of Contract or such person or persons as may be duly authorised to represent him on behalf of the Government.</p>	
D.	<p>ARCHITECT</p> <p>The term "Architect" shall be deemed to mean "The P.M." as defined above whose address unless otherwise notified is District Works Officer , P.O. Box 42267, NAIROBI.</p>	
	Carried to collection	

ITEM	DESCRIPTION	AMOUNT
A	QUANTITY SURVEYOR The term "Quantity Surveyor" shall be deemed to mean "The P.M." as defined above whose address unless otherwise notified is District Works Officer, P.O. Box 42267, NAIROBI.	
B	ELECTRICAL ENGINEER The term "Electrical Engineer" shall be deemed to mean "The P.M." as defined above whose address unless otherwise notified is District Works Officer, P.O. Box 42267, NAIROBI.	
C	MECHANICAL ENGINEER The term "Mechanical Engineer" shall be deemed to mean "The P.M." as defined above whose address unless otherwise notified is District Works Officer, P.O. Box 42267, NAIROBI.	
D	STRUCTURAL ENGINEER The term "Structural Engineer" shall be deemed to mean "The P.M." as defined above whose address unless otherwise notified is District Works officer, P.O. Box 42267, NAIROBI.	
E	FORM OF CONTRACT The Form of Contract shall be as stipulated in the Republic of Kenya's Standard Tender Document for Procurement of Building Works(2000 Edition) included herein The Conditions of Contract are also included herein <i>Conditions of Contract</i> These are numbered from 1 to 37 as set out in pages 18 to 38 of these tender documents. Particulars of insertions to be made in the Appendix to the Contract Agreement will be found in the Particular Preliminaries part of these Bills of Quantities	
	<i>Carried to collection</i>	

ITEM	DESCRIPTION	AMOUNT
A	<p>BOND.</p> <p>The Contractor shall find and submit on the Form of Tender an approved bank who will be willing to be bound to the Government in an amount equal to five per cent (5) of the Contract amount for the due performances of the Contract up to the date of completion as certified by the PROJECT MANAGER and who will, when and if called upon, sign a Bond to that effect on the relevant standard form included herein. (without the addition of any limitations) on the same day as the Contract Agreement is signed, by the Government, the Contractor shall furnish within seven days another Surety to the approval of the Government.</p>	
B	<p>PLANT, TOOLS AND VEHICLES</p> <p>Allow for providing all scaffolding, plant, tools and vehicles required for the works except in so far as may be stated otherwise herein and except for such items specifically and only required for the use of nominated Sub-Contractors as described herein. No timber used for scaffolding, formwork or temporary works of any kind shall be used afterwards in the permanent work.</p>	50,000.00
C	<p>TRANSPORT.</p> <p>Allow for transport of workmen, materials, etc., to and from the site at such hours and by such routes as may be permitted by the competent authorities.</p>	
D	<p>MATERIALS AND WORKMANSHIP.</p> <p>All materials and workmanship used in the execution of the work shall be of the best quality and description unless otherwise stated. The Contractor shall order all materials to be obtained from overseas immediately after the Contract is signed and shall also ensure they are onsite when required for use in the works. The Bills of Quantities shall not be used for the purpose of ordering materials.</p>	
E	<p>SIGN FOR MATERIALS SUPPLIED.</p> <p>The Contractor will be required to sign a receipt for all articles and materials supplied by the PROJECT MANAGER at the time of taking deliver thereof, as having received them in good order and condition, and will thereafter be responsible for any loss or damage and for replacements of any such loss or damage with articles and/or materials which will be supplied by the PROJECT MANAGER at the current market prices including Customs Duty and V.A.T., all at the Contractor's own cost and expense, to the satisfaction of the PROJECT MANAGER</p>	
	<i>Carried to collection</i>	50,000.00

ITEM	DESCRIPTION	AMOUNT
A	STORAGE OF MATERIALS The Contractor shall provide at his own risk and cost where directed on the site weather proof lock-up sheds and make good damaged or disturbed surfaces upon completion to the satisfaction of the PROJECT MANAGER Nominated Sub-Contractors are to be made liable for the cost of any storage accommodation provided especially for their use.	100,000.00
B	SAMPLES The Contractor shall furnish at his own cost any samples of materials or workmanship including concrete test cubes required for the works that may be called for by the PROJECT MANAGER for his approval until such samples are approved by the PROJECT MANAGER and the PROJECT MANAGER, may reject any materials or workmanship not in his opinion to be up to approved samples. The PROJECT MANAGER shall arrange for the testing of such materials as he may at his discretion deem desirable, but the testing shall be made at the expense of the Contractor and not at the expense of the PROJECT MANAGER. The Contractor shall pay for the testing in accordance with the current scale of testing charges laid down by the Ministry of Roads, Housing and Public Works. The procedure for submitting samples of materials for testing and the method of marking for identification shall be as laid down by the PROJECT MANAGER The Contractor shall allow in his tender for such samples and tests except those in connection with nominated sub-contractors' work.	
C	GOVERNMENT ACTS REGARDING WORKPEOPLE ETC. Allow for complying with all Government Acts, Orders and Regulations in connection with the employment of Labour and other matters related to the execution of the works. In particular the Contractor's attention is drawn to the provisions of the Factory Act 1950 and his tender must include for all costs arising or resulting from compliance with any Act, Order or Regulation relating to Insurances, pensions and holidays for workpeople or so the safety, health and welfare of the workpeople. The Contractor must make himself fully acquainted with current Acts and Regulations, including Police Regulations regarding the movement, housing, security and control of labour, labour camps , passes for transport, etc. It is most important that the Contractor, before tendering, shall obtain from the relevant Authority the fullest information regarding all such regulations and/or restrictions which may affect the organisation of the works, supply and control of labour, etc., and allow accordingly in his tender. No claim in respect of want of knowledge in this connection will be entertained.	
	<i>Carried to collection</i>	100000

ITEM	DESCRIPTION	AMOUNT
A	<p>SECURITY OF WORKS ETC.</p> <p>The Contractor shall be entirely responsible for the security of all the works stores, materials, plant, personnel, etc., both his own and sub-contractors' and must provide all necessary watching, lighting and other precautions as necessary to ensure security against theft, loss or damage and the protection of the public.</p>	
B	<p>PUBLIC AND PRIVATE ROADS.</p> <p>Maintain as required throughout the execution of the works and make good any damage to public or private roads arising from or consequent upon the execution of the works to the satisfaction of the local and other competent authority and the PROJECT MANAGER</p>	
C	<p>EXISTING PROPERTY.</p> <p>The Contractor shall take every precaution to avoid damage to all existing property including roads, cables, drains and other services and he will be held responsible for and shall make good all such damage arising from the execution of this contract at his own expense to the satisfaction of the PROJECT MANAGER</p>	
D	<p>VISIT SITE AND EXAMINE DRAWINGS.</p> <p>The Contractor is recommended to examine the drawings and visit the site the location of which is described in the Particular Preliminaries hereof. He shall be deemed to have acquainted himself therewith as to its nature, position, means of access or any other matter which, may affect his tender. No claim arising from his failure to comply with this recommendation will be considered.</p>	
E	<p>ACCESS TO SITE AND TEMPORARY ROADS.</p> <p>Means of access to the Site shall be agreed with the PROJECT MANAGER prior to commencement of the work and Contractor must allow for building any necessary temporary access roads for the transport of the materials, plant and workmen as may be required for the complete execution of the works including the provision of temporary culverts, crossings, bridges, or any other means of gaining access to the Site. Upon completion of the works, the Contractor shall remove such temporary access roads; temporary culverts, bridges, etc., and make good and reinstate all works and surfaces disturbed to the satisfaction of the PROJECT MANAGER</p> <p>The Contractor should also allow for relocating existing fence (approx. 30 metres long).</p>	
	Carried to collection	

ITEM	DESCRIPTION	AMOUNT
A	<p>AREA TO BE OCCUPIED BY THE CONTRACTOR</p> <p>The area of the site which may be occupied by the Contractor for use of storage and for the purpose of erecting workshops, etc., shall be defined on site by the PROJECT MANAGER</p>	
B	<p>OFFICE ETC. FOR THE PROJECT MANAGER</p> <p>The Contractor shall provide, erect and maintain where directed on site and afterwards dismantle the site office of the standard type, complete with furniture. He shall also provide a strong metal trunk complete with strong hasp and staple fastening and two keys. He shall provide, erect and maintain a lock-up type water or bucket closet for the sole use of the PROJECT MANAGER including making temporary connections to the drain where applicable to the satisfaction of Government and Medical Officer of Health and shall provide services of cleaner and pay all conservancy charges and keep both office and closet in a clean and sanitary condition from commencement to the completion of the works and dismantle and make good disturbed surfaces. The office and closet shall be completed before the Contractor is permitted to commence the works. The Contractor shall make available on the Site as and when required by the "PROJECT MANAGER" a modern and accurate level together with levelling staff, ranging rods and 50 metre</p>	
C	<p>WATER AND ELECTRICITY SUPPLY FOR THE WORKS</p> <p>The Contractor shall provide at his own risk and cost all necessary water, electric light and power required for use in the works. The Contractor must make his own arrangements for connection to the nearest suitable water main and for metering the water used. He must also provide temporary tanks and meters as required at his own cost and clear away when no longer required and make good on completion to the entire satisfaction of the PROJECT MANAGER. The Contractor shall pay all charges in connection herewith. No guarantee is given or implied that sufficient water will be available from mains and the Contractor must make his own arrangements for augmenting this supply at his own cost. Nominated Sub-contractors are to be made liable for the cost of any water or electric current used and for any installation provided especially for their own use.</p>	100,000.00
D	<p>SANITATION OF THE WORKS</p> <p>The Sanitation of the works shall be arranged and maintained by the Contractor to the satisfaction of the Government and/or Local Authorities, Labour Department and the PROJECT MANAGER</p>	
	Carried to collection	100000

ITEM	DESCRIPTION	AMOUNT
A	<p>SUPERVISION AND WORKING HOURS</p> <p>The works shall be executed under the direction and to the entire satisfaction in all respects of the PROJECT MANAGER who shall at all times during normal working hours have access to the works and to the yards and workshops of the Contractor and sub-Contractors or other places where work is being prepared for the contract.</p>	
B	<p>PROVISIONAL SUMS.</p> <p>The term "Provisional Sum" wherever used in these Bills of Quantities shall have the meaning stated in Section A item A7(i) of the Standard Method of Measurement. Such sums are net and no addition shall be made to them for profit.</p>	
C	<p>PRIME COST (OR P.C.) SUMS.</p> <p>The term "Prime Cost Sum" or "P.C. Sum" wherever used in these Bills of Quantities shall have the meaning stated in Section A item A7 (ii) of the Standard Method of Measurement. Persons or firms nominated by the PROJECT MANAGER to execute work or to provide and fix materials or goods are described herein as Nominated Sub-Contractors. Persons or firms so nominated to supply goods or materials are described herein as Nominated Suppliers.</p>	
D	<p>PROGRESS CHART.</p> <p>The Contractor shall provide within two weeks of Possession of Site and in agreement with the PROJECT MANAGER a Progress Chart for the whole of the works including the works of Nominated Sub-Contractors ; one copy to be handed to the PROJECT MANAGER and a further copy to be retained on Site. Progress to be recorded and chart to be amended as necessary as the work proceeds.</p>	
C.	<p>ADJUSTMENT OF P.C. SUMS.</p> <p>In the final account all P.C. Sums shall be deducted and the amount properly expended upon the PROJECT MANAGER'S order in respect of each of them added to the Contract sum. The Contractor shall produce to the PROJECT MANAGER such quotations, invoices or bills, properly receipted, as may be necessary to show the actual details of the sums paid by the Contractor. Items of profit upon P.C. Sums shall be adjusted in the final account pro-rata to the amount paid. Items of "attendance"</p>	
	<i>Carried to collection</i>	

ITEM	DESCRIPTION	AMOUNT
A	<p>ADJUSTMENT OF P.C. SUMS. Ctd.....</p> <p>Should the Contractor be permitted to tender and his tender be accepted of any work for which a P.C. Sum is included in these Bill of Quantities profit and attendance will be allowed at the same rate as it would be if the work were executed by a Nominated Sub-Contractor.</p>	
B	<p>ADJUSTMENT OF PROVISIONAL SUMS.</p> <p>In the final account all Provisional Sums shall be deducted and the value of the work properly executed in respect of them upon the PROJECT MANAGER's order added to the Contract Sum. Such work shall be valued as described for Variations, but should any part of the work be executed by a Nominated Sub-Contractor, the value of such work or articles for the work to be supplied by a Nominated Supplier, the value of such work or articles shall be treated as a P.C. Sum and profit and attendance comparable to that contained in the priced Bills of Quantities for similar items added.</p>	
C	<p>NOMINATED SUB-CONTRACTORS</p> <p>When any work is ordered by the PROJECT MANAGER to be executed by nominated sub-contractors, the Contractor shall enter into sub-contracts and shall thereafter be responsible for such sub-contractors in every respect. Unless otherwise described the Contractor is to provide for such Sub-Contractors any or all of the facilities described in these Preliminaries. The Contractor should price for these with the nominated Sub-contract Contractor's work concerned in the P.C. Sums under the description "add for Attendance".</p>	
D	<p>DIRECT CONTRACTS</p> <p>Notwithstanding the foregoing conditions, the Government reserves the right to place a "Direct Contract" for any goods or services required in the works which are covered by a P.C. Sum in the Bills of Quantities and to pay for the same direct. In any such instances, profit relative to the P.C. Sum the priced Bills of Quantities will be adjusted as described for P.C. Sums and allowed.</p>	
	<i>Carried to collection</i>	

ITEM	DESCRIPTION	AMOUNT
A	ATTENDANCE UPON OTHER TRADESMEN, ETC. The Contractor shall allow for the attendance of trade upon trade and shall afford any tradesmen or other persons employed for the execution of any work not included in this Contract every facility for carrying out their work and also for use of his ordinary scaffolding. The Contractor, however, shall not be required to erect any special scaffolding for them. The Contractor shall perform such cutting away for and making good after the work of such tradesmen or persons as may be ordered by the PROJECT MANAGER and the work will be measured and paid for to the extent executed at rates provided in these Bills.	
B	INSURANCE The Contractor shall insure as required in Clause 30 of the Conditions of Contract. No payment on account of the work executed will be made to the Contractor until he has satisfied the PROJECT MANAGER either by production of an Insurance Policy or and Insurance Certificate that the provision of the foregoing Insurance Clauses have been complied with in all respects. Thereafter the PROJECT MANAGER shall from time to time ascertain that premiums are duly paid up by the Contractor who shall if called upon to do so, produce the receipted premium renewals for the PROJECT MANAGER's inspection.	
C	PROVISIONAL WORK All work described as "Provisional" in these Bills of Quantities is subject to remeasurement in order to ascertain the actual quantity executed for which payment will be made. All "Provisional" and other work liable to adjustment under this Contract shall left uncovered for a reasonable time to allow all measurements needed for such adjustment to be taken by the PROJECT MANAGER. Immediately the work is ready for measuring, the Contractor shall give notice to the PROJECT MANAGER. If the Contractor makes default in these respects he shall if the PROJECT MANAGER so directs uncover the work to enable all measurements to be taken and afterwards reinstate at his own expense.	
D	ALTERATIONS TO BILLS, PRICING, ETC. Any unauthorised alteration or qualification made to the text of the Bills of Quantities may cause the Tender to be disqualified and will in any case be ignored. The Contractor shall be deemed to have made allowance in his prices generally to cover any items against which no price has been inserted in the priced Bills of Quantities. All items of measured work shall be priced in detail and the Tenders containing Lump Sums to cover trades or groups of work must be broken down to show the price of each item before they will be accepted.	
	<i>Carried to collection</i>	

ITEM	DESCRIPTION	AMOUNT
A	BLASTING OPERATIONS Blasting will only be allowed with the express permission of the PROJECT MANAGER in writing. All blasting operations shall be carried out at the Contractor's sole risk and cost in accordance with any Government regulations in force for the time being, and any special regulations laid down by the PROJECT MANAGER governing the use and storage of explosives.	
B	MATERIALS ARISING FROM EXCAVATIONS Materials of any kind obtained from the excavations shall be the property of the Government. Unless the PROJECT MANAGER directs otherwise such materials shall be dealt with as provided in the Contract. Such materials shall only be used in the works, in substitution of materials which the Contractor would otherwise have had to supply with the written permission of the PROJECT MANAGER. Should such permission be given, the Contractor shall make due allowance for the value of the materials so used at a price to be agreed.	
C	PROTECTION OF THE WORKS. Provide protection of the whole of the works contained in the Bills of Quantities, including casing, casing up, covering or such other means as may be necessary to avoid damage to the satisfaction of the PROJECT MANAGER and remove such protection when no longer required and make good any damage which may nevertheless have been done at completion free of cost to the Government.	
D	REMOVAL OF RUBBISH ETC. Removal of rubbish and debris from the Buildings and site as it accumulates and at the completion of the works and remove all plant, scaffolding and unused materials at completion.	
E	WORKS TO BE DELIVERED UP CLEAN Clean and flush all gutters, rainwater and waste pipes, manholes and drains, wash (except where such treatment might cause damage) and clean all floors, sanitary fittings, glass inside and outside and any other parts of the works and remove all marks, blemishes, stains and defects from joinery, fittings and decorated surfaces generally, polish door furniture and bright parts of metalwork and leave the whole of the buildings watertight, clean, perfect and fit for occupation to the approval of the PROJECT MANAGER	
	<i>Carried to collection</i>	

ITEM	DESCRIPTION	AMOUNT
A.	GENERAL SPECIFICATION. For the full description of materials and workmanship, method of execution of the work and notes for pricing, the Contractor is referred to the Ministry of Roads, Public Works and Housing General Specification dated 1976 or any subsequent revision thereof which is issued as a separate document, and which shall be allowed in all respects unless it conflicts with the General Preliminaries, Trade Preambles or other items in these Bills of Quantities.	
B.	TRAINING LEVY The Contractor's attention is drawn to legal notice No. 237 of October, 1971, which requires payment by the Contractor of a Training Levy at the rate of 1/4 % of the Contract sum on all contracts of more than Kshs. 50,000.00 in value.	
C.	MATERIALS ON SITE All materials for incorporation in the works must be stored on or adjacent to the site before payment is effected unless specifically exempted by the PROJECT MANAGER. This includes the materials of the Main Contractor, Nominated Sub-Contractors and Nominated Suppliers.	
D.	HOARDING The Contractor shall enclose all the site under construction with a hoarding 2400 mm high consisting of iron sheets gauge 30 on 100 x 50 mm 2nd grade treated sawn cypress timber posts firmly secured at 1800 mm centres with two 75 x 50 mm 2nd grade treated sawn cypress timber rails. The Contractor is in addition required to take all precautions necessary for the safe custody of the works, materials, plant, public and Employer's property on the site.	100,000
E.	CONTRACTOR'S SUPERINTENDENCE/SITE AGENT The Contractor shall constantly keep on the works a literate English speaking Agent or Representative, competent and experienced in the kind of work involved who shall give his whole experience in the kind of work involved and shall give his whole time to the superintendence of the works. Such Agent or Representative shall receive on behalf of the Contractor all directions and instructions from the Project Manager and such directions shall be deemed to have been given to the Contractor in accordance with the Conditions of Contract.	
	<i>Carried to collection</i>	100000

ITEM	DESCRIPTION	AMOUNT
	<u>COLLECTION</u>	
	Brought Forward From Page GP/ 1	
	Brought Forward From Page GP/ 2	
	Brought Forward From Page GP/ 3	
	Brought Forward From Page GP/ 4	50,000.00
	Brought Forward From Page GP/ 5	100000
	Brought Forward From Page GP/ 6	
	Brought Forward From Page GP/ 7	100000
	Brought Forward From Page GP/ 8	
	Brought Forward From Page GP/ 9	
	Brought Forward From Page GP/ 10	
	Brought Forward From Page GP/ 11	
	Brought Forward From Page GP/ 12	100000
	TOTAL FOR GENERAL PRELIMINARIES CARRIED TO SUMMARY OF PRELIMINARIES	350,000.00

PROPOSED CONSTRUCTION OF SIX CLASSROOMS, ABLUTION BLOCK AND ADMINISTRATION BLOCK FOR MUKARARA MIXED SECONDARY SCHOOL IN DAGORETTI SOUTH CONSTITUENCY.

[illegible]

PROPOSED CONSTRUCTION OF SIX CLASSROOMS, ABLUTION BLOCK AND ADMINISTRATION BLOCK FOR MUKARARA MIXED SECONDARY SCHOOL IN DAGORETTI SOUTH CONSTITUENCY.

	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<u>SUBSTRUCTURES (ALL PROVISIONAL) CONT'D</u>				
	<u>Hard core Filling as described.</u>				
A	300mm Imported hardcore filling including depositing levelling and compacting in layers of 150mm maximum thickness n.e 1.5 mm.	150	cm	1,700	255,000
B	50mm thick Quarry dust blinding to surfaces of hardcore rolled smooth to receive polythen sheeting (m.s)	500	sm	150	75,000
	<u>Antitermite treatment</u>				
C	PREMISE 200CC' or other equal and approved insecticide with a ten-years guarantee to surfaces of fill and tops of foundations	500	sm	200	100,000
	<u>Damp proofing</u>				
D	1000 gauge polythene or other equal and approved plastic sheet damp proof membrane laid over blinding (measured nett- allo for laps)	500	sm	230	115,000
	<u>In-situ concrete</u>				
	<u>Mass concrete (1.4.8/38-38 mm aggregate)</u>				
E	50mm thick mass concrete class x (1:4:8) to bottoms of foundations	7	cm	8,350	58,450
	ditto to column bases	4	cm	8,350	33,400
	<u>Vibrated reinforced concrete ; 1:1.5:3/ 25-20mm);as</u>				
	<u>decribed in</u>				
F	Foundations in trenches irrespective of thickness	19	cm	14,045	266,855
	ditto 200mm thick to column bases	15		14,045	210,675
G	150mm thick bed	500	sm	1,800	900,000
	<u>Reinforcement</u>				
	<u>Bars; high yield steel; cold worked to B.S. 4461 including bends, hooks, tying wire and distance blocks of assorted diameter</u>				
	ditto 10mm to strip foundation footing	655	kgs	165	108,075
	ditto 12mm to column bases	776	kgs	165	128,040
	ditto 16mm to column stubs	840	kgs	165	138,600
	ditto 8mm to column links	210	kgs	165	34,650
	<u>Sawn formwork to insitu concrete as described:-</u>				
	to column stubs	104	sm	550	57,200
	<i>Carried to collection</i>				2,480,945

PROPOSED CONSTRUCTION OF SIX CLASSROOMS, ABLUTION BLOCK AND ADMINISTRATION BLOCK FOR MUKARARA MIXED SECONDARY SCHOOL IN DAGORETTI SOUTH CONSTITUENCY.

	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
A	<u>Mesh reinforcement ; B.S. 4483</u> Reference A142 mesh 200 x 200 mm , weight 2.22 kgs per square meter (measured net - no allowance made for laps(including bends, tying wire and distance blocks <u>Sawn formwork to insitu concrete as described:-</u>	500	sm	420	210,000
B	Edges of ground floor slab; 75 to 150mm wide <u>Foundation Walling</u>	130	lm	200	26,000
C	200mm thick approved local natural stone; roughly squared to foundation walling; bedding and jointing in cement sand (1:3) mortar and reinforced with and including 20swg x 25 mm wid hoopiron in every alternate course	344	sm	1,835	631,240
D	<u>Insitu finishings</u> 14mm thick 2 No. coatwork cement sand (1:3) render; wood floated to concrete or blockwork base to walls; external Prepare and apply three coats black bituminous paint on:-	120	sm	400	48,000
E	Rendered plinths, externally.	120	sm	400	48,000
	<i>Carried to collection</i>				963,240

PROPOSED CONSTRUCTION OF SIX CLASSROOMS, ABLUTION BLOCK AND ADMINISTRATION BLOCK FOR MUKARARA MIXED SECONDARY SCHOOL IN DAGORETTI SOUTH CONSTITUENCY.

DESCRIPTION	QTY	UNIT	RATE	AMOUNT
From page BW/1				508,000
From pageBW /2				2,480,945
From page BW/3				963,240
TOTAL FOR SUBSTRUCTURES CARRIED TO SUMMARY				3,952,185

PROPOSED CONSTRUCTION OF SIX CLASSROOMS, ABLUTION BLOCK AND ADMINISTRATION BLOCK FOR MUKARARA MIXED SECONDARY SCHOOL IN DAGORETTI SOUTH CONSTITUENCY.

[illegible]

PROPOSED CONSTRUCTION OF SIX CLASSROOMS, ABLUTION BLOCK AND ADMINISTRATION BLOCK FOR MUKARARA MIXED SECONDARY SCHOOL IN DAGORETTI SOUTH CONSTITUENCY.

	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<u>Sawn formwork to insitu concrete as described:-</u>				
A	to column sides	406	sm	600	243,600
	ditto to suspended beams sides ,soffits and slab soffits	800	sm	800	640,000
	ditto to stairs soffits	30	sm	800	24,000
	<i>To Collection</i>				907,600
	From page BW /5				3,926,470
	From Above				907,600
	TOTAL FOR FRAME CARRIED TO SUMMARY				4,834,070

PROPOSED CONSTRUCTION OF SIX CLASSROOMS, ABLUTION BLOCK AND ADMINISTRATION BLOCK FOR MUKARARA MIXED SECONDARY SCHOOL IN DAGORETTI SOUTH CONSTITUENCY.

	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<u>ELEMENT NO. 3</u>				
	<u>Natural stone walling bedded and jointed in cement and sand (1:3) mortar and reinforced with and including 20 swg x 25 mm wide hoopiron; external</u>				
A	200 mm thick reinforced with hoop iron after every two alternate courses to ground floor	648	sm	1,850	1,198,800
	ditto firstfloor walling	530	sm	1,850	980,500
	ditto 200mm thick to internal gamble fillings	47	sm	1,850	86,950
B	ditto 200mm thick eave fillings.	50	sm	1,850	92,500
C	Extra over horizontal pointing in 10mm thick rod in cement and sand (1:3) mortar to external wall	690	sm	400	276,000
	<u>Horizontal Damp Proof Course:one layer of 3-ply bituminous felt or other equal approved (measured nett-allow for laps)</u>				
D	200mm wide, B.S. 743 Type A bitumen hessian base 150 mm laps (no allowance made for laps); horizontal, 1 no. layer, bedded in cement sand (1:3) mortar	240	lm	200	48,000
TOTAL FOR EXTERNAL AND INTERNAL WALLING CARRIED TO SUMMARY					2,682,750

PROPOSED CONSTRUCTION OF SIX CLASSROOMS, ABLUTION BLOCK AND ADMINISTRATION BLOCK FOR MUKARARA MIXED SECONDARY SCHOOL IN DAGORETTI SOUTH CONSTITUENCY.

	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<u>ELEMENT NO. 4</u>				
	<u>DOORS</u>				
	<u>Standard section purpose made heavy duty glazed steel casement door in 200 x 250mm high panes prepared for glazing (m.s) complete with all requisite frame, sub-frames, mullions, transomes, fixing lugs cast on, 1 1/2 pairs heavy duty pin type hinges associated casement door lock and handles, 2 x 200mm wide x 16 gauge bottom plate, including one coat red oxide primer before fixing and mastic sealant all around as described in:</u>				
A	Door Size 28000 x 2700mm high overall Framed RHS Steel double leaf in four equal leaves	1	No	30,000	30,000
B	ditto 1500x2700mm high	11	No	15,000	165,000
C	ditto 900x2400mm high	6	No	12,000	72,000
	<u>Glazing</u>				
D	5mm Thick clear sheet glass panes over 0.1 but not exceeding 0.5 square meters; fixing with putty	6	sm	1,500	9,000
	<u>Painting and Decorations</u>				
	<u>Prepare and apply three coats oil paint full gloss to Crown Solo or other equal and approved to: -</u>				
E	General surfaces of Metal door	104	sm	350	36,400
	<u>Timber Doors</u>				
F	900x2400mm high solid core mahogany laminated timber	24	NO	8,000	192,000
G	ditto 1200x2700mm double flap timber flush doors for special toilets.	2	NO	10,000	20,000
H	<u>Wrot Cypress door frames; selected and kept clean</u> 200 x 50mm thick frames; with 2No.labours and countersunk screws	225	LM	540	121,500
I	75 x 15mm architrave	225	LM	200	45,000
J	25mm Dia quadrant beading	225	LM	100	22,500
	<u>Prepare and apply one coat wood primer on back of wood before fixing</u>				
K	Surfaces not exceeding 100mm girth	225	LM	100	22,500
	<u>Prepare, touch up primer and apply one undercoat and two coats clear varnish on wood surfaces</u>				
L	Door surfaces (measured flat both sides)	225	SM	350	78,750
M	Surfaces not exceeding 100mm girth	50	LM	80	4,000
	Carried to Collection				818,650

PROPOSED CONSTRUCTION OF SIX CLASSROOMS, ABLUTION BLOCK AND ADMINISTRATION BLOCK FOR MUKARARA MIXED SECONDARY SCHOOL IN DAGORETTI SOUTH CONSTITUENCY.

	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<u>Ironmongery</u>				
	<u>Ironmongery</u>				
	Supply and fix the following to UNION catalogue or equal and approved				
A	Two lever mortice lock complete with set lever brass handle furniture	24	NO	3,500	84,000
B	100 mm wide pressed steel butt hinges	42	PRS	330	13,860
C	100mm barrel bolt.	4	NO	250	1,000
	<u>collection</u>				98,860
	From page 8				818,650
	From page above				98,860
	TOTAL FOR DOORS CARRIED TO SUMMARY				917,510

PROPOSED CONSTRUCTION OF SIX CLASSROOMS, ABLUTION BLOCK AND ADMINISTRATION BLOCK FOR MUKARARA MIXED SECONDARY SCHOOL IN DAGORETTI SOUTH CONSTITUENCY.

[illegible]

PROPOSED CONSTRUCTION OF SIX CLASSROOMS, ABLUTION BLOCK AND ADMINISTRATION BLOCK FOR MUKARARA MIXED SECONDARY SCHOOL IN DAGORETTI SOUTH CONSTITUENCY.

	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<u>Glazing</u>				
A	5mm Thick clear sheet glass panes over 0.1 but not exceeding 0.5 square meters; fixing with putty	181	sm	1,500	271,500
	<u>Window board</u>				
B	150 x 25 mm thick window boards including bull-nosed edges and 25 x 25 mm bearer; plugged, counter sinking and flush pelleting.	40	lm	350	14,000
	<u>Window cill</u>				
C	125 x 20 mm thick quarry tile cill with one curved edge including bedding and pointing in cement and sand (1:3) mortar	130	lm	350	45,500
D	20 x 10 mm impregnated sawn cypress timber ground plugged	130	lm	150	19,500
	<u>Painting and Decorations</u>				
	<u>Touch up premier, prepare and apply one undercoat and two finishing coats first quality gloss oil paint as 'Crown' or other equal approved manufacturer on:</u>				
E	Surfaces of small panes casement windows including burglar proofing (measured one side over glazing)	100	sm	350	35,000
	<i>Carried to collection</i>				385,500

PROPOSED CONSTRUCTION OF SIX CLASSROOMS, ABLUTION BLOCK AND ADMINISTRATION BLOCK FOR MUKARARA MIXED SECONDARY SCHOOL, IN DAGORETTI SOUTH CONSTITUENCY.

[illegible]

PROPOSED CONSTRUCTION OF SIX CLASSROOMS, ABLUTION BLOCK AND ADMINISTRATION BLOCK FOR MUKARARA MIXED SECONDARY SCHOOL IN DAGORETTI SOUTH CONSTITUENCY.

[illegible]

PROPOSED CONSTRUCTION OF SIX CLASSROOMS, ABLUTION BLOCK AND ADMINISTRATION BLOCK FOR MUKARARA MIXED SECONDARY SCHOOL IN DAGORETTI SOUTH CONSTITUENCY.

	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<u>Floor finishes</u> <u>20mm thick, 2 No. coat work terrazzo; approved colour; cement and marble chippings (1:2); machine polished; to concrete or blockwork base generally to: -</u>				
A	To Floors level; internal	1000	sm	2450	2,450,000.00
B	Skirtings; 100mm wide with rounded junction with wall finish and coved junction with floor finish	478	lm	400	191,200.00
	<u>Beds or Backings</u> <u>Screed; cement and sand (1:3)</u>				
C	20mm thick floor screed; wood floated to receive terrazzo paving (m/s)	600	sm	400	240,000.00
	<u>Ceiling finishes</u> <u>Wrot cypress</u>				
D	75 x 25mm moulded cornice	478	lm	350	167,300.00
	<u>Approved sawn softwood; second grade; pressure impregnated.</u>				
E	50 x 50mm brandering	1570	lm	300	471,000.00
	<u>Chip board</u>				
G	12mm thick plain chip-board ceiling board nailed to timber brandering (m/s); nails punched and puttied	500	sm	1300	650,000.00
	<u>Painting and Decorations</u> <u>Prepare and apply one undercoat and three coats of first quality emulsion paint to the following surfaces</u> <u>To wood surfaces</u>				
H	Chip-board ceiling boards	500	sm	350	175,000.00
I	Moulded cornice not exceeding 100mm girth	478	lm	100	47,800.00
Carried to Collection					4,392,300

PROPOSED CONSTRUCTION OF SIX CLASSROOMS, ABLUTION BLOCK AND ADMINISTRATION BLOCK FOR MUKARARA MIXED SECONDARY SCHOOL IN DAGORETTI SOUTH CONSTITUENCY.

[illegible]

PROPOSED CONSTRUCTION OF SIX CLASSROOMS, ABLUTION BLOCK AND ADMINISTRATION BLOCK FOR MUKARARA MIXED SECONDARY SCHOOL IN DAGORETTI SOUTH CONSTITUENCY.

	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<u>ROOFING CONSTRUCTION, COVERING AND RAIN WATER DISPOSAL</u>				
	<u>Galvanized steel IT5 box profile sheets; 28 gauge; prepainted</u>				
A	Roof covering; 150mm laps on one end and one and a half corrugation side lap; and fixing as necessary to steel purlins (m/s) on steel trusses (m/s) at 1200mm max. c/c all laid to fall at 22.5°	690	sm	1400	966,000.00
	<u>Accessories, fixing as necessary to roof sheets</u>				
B	Standard ridge sheet	115	lm	400	46,000.00
C	Ditto valley / hip sheets	18	lm	400	7,200.00
	<u>Structural timber</u>				
	<u>Grade II presure impregnate sawn cypress in;</u>				
	<u>Framed timberwork</u>				
	<u>The following in trusses including scafed or dovetailed jointing, hoisted and fixed 3000/6000mm above ground floor slab</u>				
D	150x50mm rafter	456	lm	460	209,760.00
E	150x50mm Tie beam	380	lm	460	174,800.00
F	100x50mm Struts or ties	722	lm	460	332,120.00
G	150x50mm King post	86	lm	460	39,560.00
	<u>Unframed timber work</u>				
H	150x50mm Common rafter	192	lm	550	105,600.00
J	75x50mm Purlins	580	lm	550	319,000.00
K	220x50mm Ridge board	55	lm	550	30,250.00
L	100x50mm Wall plate fixed with and including 200mm long x 12mm diameter anchor bolts cast into beam at 1800mm centres, provide for all necessart drilling, threading, nuts and washers	130	lm	450	58,500.00
	<u>In grade II treated wrot cypress</u>				
M	225x25mm fascia or verge board	130	lm	350	45,500.00
N	25mm Thick prime grade tounge and grooved eaves or verge boarding in 100mm wide strips on and including 50x50mm sawn cypress brandaring at 600mm centres both direction	78	sm	2000	156,000.00
	<i>Carried to collection</i>				2,490,290.00

**PROPOSED CONSTRUCTION OF SIX CLASSROOMS, ABLUTION BLOCK AND ADMINISTRATION BLOCK FOR MUKARARA MIXED
SECONDARY SCHOOL IN DAGORETTI SOUTH CONSTITUENCY.**

	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<u>RAINWATER DISPOSAL</u>				
	<u>Rain water goods</u>				
	<u>24g Galvanised mild steel sheeting; all welds ground smooth</u>				
A	150 x 100mm box gutter including soldered joints in the running length fixed to fascia board with and including brackets at approved centers	130	lm	950	123,500.00
B	Extra; for blocked ends with 75mm dia.outlet 100mm long	13	No	500	6,500.00
C	Extra; for 90° bends	13	No	500	6,500.00
D	Extra; 75mm dia.outlet 100mm long	13	No	500	6,500.00
E	75mm dia. rainwater downpipe fixed with and including mild steel straps at 900mm centres, plugged and screwed to wall	55	lm	750	41,250.00
F	Extra; swanneck bend	13	No	500	6,500.00
G	Extra; horse shoe bend	13	No	500	6,500.00
	<u>Painting and Decorations</u>				
	<u>On Woodwork</u>				
	<u>Prepare and apply one undercoat and two coats of 'CROWN SOLO' or other equal and approved super gloss oil paint to:-</u>				
H	Fascias; 200 to 300mm girth; external	130	lm	200	26,000.00
	<u>On Metal work</u>				
	<u>Prepare and apply one approved etching primer, one undercoat and two coats of 'CROWN SOLO' or other equal and approved super gloss oil paint to:-</u>				
I	General surfaces of gutters; over 300mm girth external	60	sm	350	21,000.00
	<i>Carried to collection</i>				244,250.00

PROPOSED CONSTRUCTION OF SIX CLASSROOMS, ABLUTION BLOCK AND ADMINISTRATION BLOCK FOR MUKARARA MIXED SECONDARY SCHOOL IN DAGORETTI SOUTH CONSTITUENCY.

	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<u>Tongue & Grooved Timber surfaces</u>				
	<u>Prepare and apply three coats of 'CROWN SOLO' or other equal and approved polyurethane varnish to:-</u>				
A	Surfaces of eaves; over 300mm girth external	78	sm	350	27,300.00
	<u>To collection</u>				27,300.00
	<u>COLLECTION</u>				
	From page MH / 16				2,490,290.00
	From page MH / 17				244,250.00
	From Above				27,300.00
	TOTAL FOR ROOFING CARRIED TO SUMMARY				2,761,840.00

PROPOSED CONSTRUCTION OF SIX CLASSROOMS, ABLUTION BLOCK AND ADMINISTRATION BLOCK FOR MUKARARA MIXED SECONDARY SCHOOL IN DAGORETTI SOUTH CONSTITUENCY.

	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<u>SUMMARY</u>				
ELEMENT NO.	TITLE		PAGE NO.		K.SHS.
1	SUBSTRUCTURE (ALL PROVISIONAL)		BW/4		3,952,185
2	R.C. SUPERSTRUCTURE		BW/6		4,834,070
3	EXTERNAL & INTERNAL WALLING		BW/7		2,682,750
4	DOORS		BW/9		917,510
5	WINDOWS		BW/12		1,239,500
6	FINISHES		BW/15		6,238,800
7	ROOFING		BW/18		2,761,840
TOTAL BUILDERS WORKS TO GRAND SUMMARY					22,626,655

**PROPOSED CONSTRUCTION OF SIX CLASSROOMS, ABLUTION BLOCK AND ADMINISTRATION BLOCK FOR
MUKARARA MIXED SECONDARY SCHOOL IN DAGORETTI SOUTH CONSTITUENCY.**

ITEM	DESCRIPTION	QTY	UNIT	RATE	K.SHS
	<u>PRIME COSTS & PROVISIONAL SUMS</u>				
	<u>PROVISIONAL SUMS</u>				
	<u>The following provisional sums are to be measured on completion and priced in accordance with the rates contained in these bills of quantities or prorata thereto or deducted in whole if not required</u>				
A	Allow for Kenya Shillings Three hundred thousands (Kshs 300,000.00) only for Electrical Installations		ITEM		300,000.00
B	Allow for Kenya Shillings three hundred thousands (Kshs 300,000.00) only for Mechanical works and Installations		ITEM		300,000.00
C	Allow for Kenya Shillings Five Hundred Thousand (Kshs 500,000.00) only for Contingencies		ITEM		500,000.00
	TOTAL FOR P.C. & PROVISIONAL SUMS CARRIED TO GRAND SUMMARY				1,100,000.00

PROPOSED CONSTRUCTION OF SIX CLASSROOMS, ABLUTION BLOCK AND ADMINISTRATION BLOCK FOR MUKARARA MIXED SECONDARY SCHOOL IN DAGORETTI SOUTH CONSTITUENCY.

ITEM	DESCRIPTION	SHS	SHS
		FOR OFFICIAL USE	FOR CONTRACTOR'S USE
	MAIN SUMMARY		
1	PARTICULAR PRELIMINARIES	680,000	
2	GENERAL PRELIMINARIES	350,000	
3	BUILDERS WORK	22,626,655	
4	PROVISIONAL SUMS PS/1	1,100,000	
	TOTAL CARRIED TO FORM OF TENDER KSHS	24,756,655	
<p>CONTRACTOR'S NAME,.....</p> <p>ADDRESS,.....</p> <p>DATE,.....</p> <p>SIGNATURE,.....</p> <p>WITNESS NAME,.....</p> <p>ADDRESS.....</p> <p>DATE,</p> <p>SIGNATURE,</p>			



Republic of Kenya

MINISTRY OF EDUCATION

STATE DEPARTMENT OF EARLY LEARNING AND BASIC EDUCATION

Telegrams: "SCHOOLING", Nairobi
Telephone: Nairobi 020 2453699
Email: rcenalrobi@gmail.com
cdenalrobi@gmail.com

REGIONAL DIRECTOR OF EDUCATION
NAIROBI REGION
NYAYO HOUSE
P.O. Box 74629 - 00200
NAIROBI

When replying please quote

Ref: RCE/NRB/GEN/VOL.1

DATE: 13th October, 2020

The Hon. John K.J Kiarie, MP
Dagoretti South Constituency
P. O. Box 41842-00100
NAIROBI.


RE: CONSTRUCTION OF MUKARARA AND KAGIRA MIXED SECONDARY SCHOOLS

This office is in receipt of your letter dated 8th October, 2020 requesting for approval to construct the two mixed Secondary Schools in Dagoretti South Constituency.

We are pleased to inform you that there is no objection on the construction since the two schools will go a long way in enhancing the transition rates in Dagoretti South Constituency.

Kindly liaise with the Sub-County Education Office for professional support and assessment for registration by County Education Board once the construction is completed.

OBIERO J. O
REGIONAL DIRECTOR OF EDUCATION
NAIROBI.



Cc: Principal Secretary
Ministry of Education
State Department of Early Learning and Basic Education.



Mukarara Primary School.

PO BOX 21353 – 00505

NAIROBI

4/8/2020

TO THE NG-CDF MANAGER,
DAGORETTI SOUTH CONSTITUENCY.

Dear Sir/ Madam.

**REF: ESTABLISHMENT OF A SECONDARY SCHOOL AT MUKARARA
PRIMARY SCHOOL.**


With reference to our BOM Meeting Held on 15th June 2018, the members wished if there would be an establishment of a secondary school on the vast piece of land that the school has.

Our school is sitting on a 10-acre piece of land. The committee wished if the land was used wisely, then most of our pupils who complete primary education will join the secondary school with ease.

The issue was also mentioned in our BOM meeting held on 28th January 2020. We have attached copies of our meeting minutes


We humbly ask your able to put into consideration our humble request.

Yours faithfully



Beatrice K. Malweyi.

Headteacher/ Secretary BOM



MUKARARA PRIMARY SCHOOL

BOM MEETING HELD ON 28.01.2020

Members present

1. Mrs. Kemboi Beatrice- H/ teacher/ Secretary
2. Juliet Kinyua – Chairperson
3. James Machua – Treasurer
4. Lucia Kihia – Education Board
5. Samuel Mugo – P.A Chairman
6. Symon Maina – D/ head teacher
7. Joyce Mulwa – G4 representative
8. Joseph Mbuki Kinyanjui – PCEA Mukarara
9. Solomon Kasule – BOM Member
10. Lucy Gitonga – PCEA Mukarara
11. Hannah Kanyi – Class representative 8
12. Elizabeth Nekesa – Class representative 7
13. Joan Imbala – Class representative 6
14. Peter Ngugi – Teacher's representative
15. Jane Karanja – BOM Member

AGENDA

1. Opening prayers
2. Welcome and introduction
3. Reading and confirmation of previous minutes.
4. Matters arising.
5. BOM –Committees
6. NG-CDF renovations.
7. Academics.
8. Class meetings and AGM.
9. School funds.
10. A.O.B

Min 01/01/2020 PRAYERS

The meeting started with prayers led by Samuel Mugo at 10.15am.

Min 2/01/2020- WELCOME AND INTRODUCTION

The head teacher welcomed all the members present after which those present did self-introduction.

Min 03/01/2020 - READING AND CONFIRMATION OF PREVIOUS MINUTES

The meeting of the previous meeting were led and confirmed.

Proposer: Joan Imbala

Seconded: Solomon Kasule

Min 04/01/2020 - MATTERS ARISING

P.C.E.A Church has forwarded its members to the BOM and the BOM Chairperson Juliet Kinyua.

She automatically become signatory to Schools accounts.

Min 05/01/2020- BOM COMMITTEES

The following member were appointed to be in charge of various committees as stipulated in the Basic Education Act.

1. Academic committee

- i) Joseph Mbuki Kinyanjui
Proposer: Hannah Kanyi
Seconded: Elizabeth Nekesa.

- ii) Joyce Mulwa
Proposer: Joan Imbala
Seconded: Hannah Kanyi

2. Environment committee

- i) Solomon Kasule
Proposer: Samuel Mugo
Seconded: Elizabeth Nekesa
- ii) Lucy Githang'a
Proposer: Hannah Kanyi
Seconded: Joyce Mulwa

3. Finance committee

Automatic: the head teacher – Mrs. Kemboi

: The Chairperson – Juliet Kinyua

: The treasurer – James Machua

: P.A Chairperson – Samuel Mugo

4. Food and nutrition/ Feeding programme.

i) P.A Chairperson – Samuel Mugo

ii) Parent representative – Jane Karanja

Min 06/01/2020: RENNOVATIONS

The first phase renovation of 5 classrooms was done but the work is unsatisfactory and this would be followed up through the constituency office for the roofs are leaking. Retention fee for this project has not yet been released. 6 out of 8 classrooms have been renovated at a cost of 4.4 million shillings while the remaining 2 are almost done at a cost not known.

The NG-CDF Dagoretti South is also building a community kitchen which will be used for food preparation and distribution to other schools in the constituency.

Learners will be paying through M-pesa using a tap to eat gadget.

There is also a plan to construct 8 pit latrines by the CDF with a proposal of putting up a tank near the toilets.

The committee also revised what had been discussed during the BOM meeting in 2018 regarding the sourcing of a financial ^{support} to put up a secondary school so that the 100% transition of the pupils is realized.

The executive was asked to visit the CDF office or Write a letter for consideration

Min 07/01/2020: ACADEMICS

The main objective of School reestablishment is academic. The BOM should strategize on how to improve academic standards bearing in mind that last year's candidates performed very properly taking position 16/16.

Main challenges identified included:

- i) Lack of parental commitment in Children wellbeing.
- ii) Lack of good nutritional food for majority of the learners.
- iii) Parents not paying up school support fee of Ksh 200 until the learners are sent home.

iv) Lack of innovation for learners and teachers.

Class representatives were given the tasks of discussing strategies of improving academic standards in the class minutes scheduled as below:

Friday 31ST January – std 8

Monday 3rd February – std 7,6,and 5

Wednesday 5th February – Grades 1,2,3 and 4

During class meetings, the class representative will chair the meeting.

It was proposed that the School set aside an academic day.

The date for the AGM will be set in Goveretion with the area MP John Kiarie to conside with the handing over of the build and renovated facilities.

Min 09/01/2020: SCHOOL FUNDS

The board unanimously agreed to continue with the levy of Kdh 200 per child per month to support School activities.

The government in term one has given ksh 100 per child in account 1 and ksh 344 in account 2. GPA.

The head teacher informed the board that the School owes the School supplies some money from last term bills on stationary supplied and that this term she had also delivered some for to be paid with the current fund.

Members agreed that the School need to employ more teachers and improve infrastructures especially the desks and chairs for lower grades. Members present adopted the presented budget and agreed that there was need to look for well-wishers to sponsors meals for our learners who are going hungry hence not concentrating during lessons.

Min 10/01/2020 A.O.B

- P.C.E.A Mukarara used to sponsor a teacher and headteacher committed to writing a letter on the same as the funds had been directed to assist needy learners.
- During AGM local leaders would be invited.
- Class representatives were challenged to know their parent and work tirelessly to support the School. The greatest challenge in the area is Parents mind set.
- The Church-PCEA Mukarara was tasked with the responsibility of conducting guidance to the parents mentally and spiritually.
- The School needs WI-FI for ICT lessons and feedback giving to the government as this is the new trend.
- The head teacher appreciated the Church- PCEA Mukarara for the generous contribution of 70 chairs.
- The board agreed that support staff will be contracted for a period of 3 months through a written document which can be renewed.
- The staff needs to apply for the jobs at the end of the term for renewal.
- PCEA Mukarara through the youth pastor has been allowed to take care of the learner's spiritual welfare from 3.10 to 4.30 pm every Tuesday.
- Member were requested to be on the lookout and facilitate learner's transition to Secondary School and colleges.
- Teacher's motivation was discussed and it was agreed that a letter of appreciation would be given to deserving teaching inclusive of a token. This may also include an outing at the end of the term.
- Need to bring together ALUMNI of this School was discussed for they can be of great impact to the School. Proposal was that a cup of tea would be prepared to bring them together.

Without any other business to transact the meeting ended with prayers led by Lucy Githang'a.

CONFIRMED

Chairman: JAMES MAETHUA

[Signature]
FOR
CHAIRMAN

Secretary: Beatrice K. Malweyi

[Signature]



MUKARARA PRIMARY SCHOOL B.O.M MEETING HELD
ON 15/06/2018 IN THE HEADTEACHER'S OFFICE.

MEMBERS PRESENT.

- 1) Mrs KEMBOI – H/TR Secretary
- 2) Mr Maina – D/HT
- 3) Samuel Mugo
- 4) Samuel Kigotho
- 5) Gerald Muchugia – Chairman
- 6) James Macharia – Treasurer
- 7) Mr Peter Ngugi
- 8) Felister Wangui
- 9) Justus Mochire
- 10) Daniel M. Kariuki
- 11) Jane N. Karanja
- 12) Lucy Githang'a
- 13) Solomon Kasule
- 14) Rose Wanjiru.

Confirmed
[Signature]



The meeting started with prayers.

AGENDA.

1. Reading and confirmation of previous minutes
2. Matters arising
3. F.P.E funds
4. School garden
5. Security
6. School strategic plan.
7. A.O.B.

MIN 01/06/2018 : READING AND CONFIRMATION OF PREVIOUS MINUTES.

The minutes were read by the secretary H/TR and were proposed by Lucy Githang'a and seconded by Solomon Kasule.

MIN 02/06/2018 : MATTERS ARISING.

Class meeting were held as planned and parents were cooperative.

- (1) The AGM was held and C.S.O was in attendance.
- (2) However it was realized that class issues were raised during the AGM and this will hence forth not be allowed.
- (3) BOM members were challenged to be attending class meetings.
- (4) Class meeting attendance for grade 2 and Std 4 was very low.
- (5) To enhance payments by parents Ksh 200 agreed during the AGM to help the school to run members agreed that only learner who have paid for meals will be fed.
- (6) Members assigned to visit next and MP had not yet visited them.
- (7) On NEMIS registration majority of the parents had not yet forwarded birth certificate for their children.
- (8) Proposed class meeting were scheduled as follows :-

Classes 6,7,8 – 4 and 5 and grade 1,2 and 3 in early July

MIN 03/06/2018 : F.P.E FUNDS.

The headteacher reported to the members that the school had not received funds from the government because the banker Standard Chartered Bank had closed the account reasons being inavailability of school's registration certificate.

She explained the steps she had made to activate the account by visiting the Sub-County director of Education as well as the county directors office.

The bank received a memorandum to be signed with the school that has been done but the account is still dormant.

MIN 06/06/2018 :- SCHOOL STRATEGIC PLAN.

Areas identified as to requiring immediate action included

- 1) Water points that are leaking.

The taps need to be replaced with durable ones

- 2) Election of water tank at the lower classroom.

The tank was provided by area M.P

- 3) Placing of flag post near the quadrangles

- 4) Renovation of entrance to the learner's toilets to reduce water logging

Other areas to be attended to include :-

- 1) Renovation of science room near the senior teacher's office.

- 2) Replacing of window panes to reduce coldness in the classes so as to make the learning environment better.

- 3) The whole school need painting when funds are available.

- 4) Leaking roofs in some classes that have asbestos roofing.

- 5) Long term project of existing perimeter wall for security purpose.

- 6) long term project of setting aside a piece of land for the construction a secondary school

It was realized that a new strategic plan need to be drafted to mobilize resources for the school.

MIN 07/06/2018 A.O.B

The following issues were discussed.

- (i) The school will agreed hold fund raising in March 2019.
- (ii) There is a well with enough water near the kitchen that can be used to farm in the green house.
- (iii) Dusting of the school compound to reduce mad.
- (iv) Felistus and Mochine were given the responsibility of following this up.
- (v) Mochine was assigned the responsibility of contacting the person in charge of education in the county.
- (vi) Our security man needed uniform and security room redesigned.

- (vii) Modifying the office for the secretaries office.
- (viii) Establishment of mud scrappers.
- (ix) Youth using school facility help in clean up.
- (x) The school clerk had been deployed to city hall hence need for school's clerk.
- (xi) Headteacher and deputy headteacher office door to be replaced and metallic one to be placed at the science room.

All classes requires metallic door with time.

It was agreed that the next meeting would be held in term 3 and the meeting ended with prayers led by Jane.

CONFIRMED

CHAIRMAN: GERALD MUCHUGIA SIGN: [Signature]

SECRETARY: BEATRICE K. NIALWEYI SIGN: [Signature]

